# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT28872

## APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2017-18, Date: 01.02.2018

**Package No. 01 (Package consists of 18 works)**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of D NARAHARI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 86 | KSRRB M200-13.1. Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled materia | cum | 542.7 | Rupees Five Hundred Forty Two and Seventy Paise Only |
| 2 | 8205.8 | KSRRB 200-8. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of s | Sqm | 7.2 | Rupees Seven and Twenty Paise Only |
| 3 | 11186.29 | KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&IWTD SR 2016-17) | Cum | 228.6 | Rupees Two Hundred Twenty Eight and Sixty Paise Only |
| 4 | 267.54 | KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and | Cum | 225 | Rupees Two Hundred Twenty Five Only |
| 5 | 1274 | Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,w | m | 1646.1 | Rupees One Thousand Six Hundred Forty Six and Ten Paise Only |
| 6 | 131.99 | KSRB 2.6 : Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.specification. No. KBS 2.10.2(P.No.6,sl.No.2.13 of PW, P&IWTD SR 20 | Cum | 2423.7 | Rupees Two Thousand Four Hundred Twenty Three and Seventy Paise Only |
| 7 | 114.66 | KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specific | Cum | 86.4 | Rupees Eighty Six and Forty Paise Only |
| 8 | 172.8 | KSRB13-3.6 : Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings ( earth work in trenches to be measured and paid for separately ) including cost of all materials, labour charges, HOM of eq | m | 490.5 | Rupees Four Hundred Ninety and Fifty Paise Only |
| 9 | 1229.39 | Removing and resetting of footpath slab (P.No.265, I.No.37.56 of PW, P&IWTD SR 2016-17) | Sqm | 142.2 | Rupees One Hundred Forty Two and Twenty Paise Only |
| 10 | 18112.46 | Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No.25, I.No.5.33 of PW, P&IWTD SR 2016-17) | Sqm | 86.4 | Rupees Eighty Six and Forty Paise Only |
| 11 | 11104.01 | Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 7.5cms thick (P.No.25, I.No.5.31.1 of PW, P&IWTD SR 2016-17) | Sqm | 712.8 | Rupees Seven Hundred Twelve and Eighty Paise Only |
| 12 | 591.31 | Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 10cms thick (P.No.25, I.No.5.31.2 of PW, P&IWTD SR 2016-17) | Sqm | 884.7 | Rupees Eight Hundred Eighty Four and Seventy Paise Only |
| 13 | 411.56 | KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as | Cum | 4752.9 | Rupees Four Thousand Seven Hundred Fifty Two and Ninety Paise Only |
| 14 | 735.89 | KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P. | Sqm | 109.8 | Rupees One Hundred Nine and Eighty Paise Only |
| 15 | 44.6 | KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not ex | cum | 5709.6 | Rupees Five Thousand Seven Hundred Nine and Sixty Paise Only |

For Benaka Developers And Projects Pvt Ltd.
(Formerly Prajval Properties Pvt. Ltd.)

Signature of the contractor
Authorised Signatory



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of D NARAHARI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 16 | 578.12 | KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers no | Cum | 5295.6 | Rupees Five Thousand Two Hundred Ninety Five and Sixty Paise Only |
| 17 | 36.56 | Providing laying plain/ reinforced cement concrete M20 Grade for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc. complete as per approved drawing and design MORTH specification No. 1500, 1700, 2200. (P.No.265, I.No. | Cum | 11418.3 | Rupees Eleven Thousand Four Hundred Eighteen and Thirty Paise Only |
| 18 | 39 | KSRB 4-6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specifcation | Sqm | 261.9 | Rupees Two Hundred Sixty One and Ninety Paise Only |
| 19 | 285.6 | KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surfaces such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, I | Sqm | 333 | Rupees Three Hundred Thirty Three Only |
| 20 | 63.3 | Providing and laying cement concrete using 20mm and downsize granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, | Cum | 6450.3 | Rupees Six Thousand Four Hundred Fifty and Thirty Paise Only |
| 21 | 6.9 | KSRB - 4.9.2: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever nec | tonne | 68805 | Rupees Sixty Eight Thousand Eight Hundred Five Only |
| 22 | 490.51 | Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides e | sqm | 1861.2 | Rupees One Thousand Eight Hundred Sixty One and Twenty Paise Only |
| 23 | 580.44 | Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides e | sqm | 5347.5 | Rupees Five Thousand Three Hundred Forty Seven and Fifty Paise Only |
| 24 | 603.9 | Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite m | Cum | 6156 | Rupees Six Thousand One Hundred Fifty Six Only |
| 25 | 6039 | Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(P.No.177, I.No.22. | sqm | 102.6 | Rupees One Hundred Two and Sixty Paise Only |
| 26 | 8592.9 | KSRRB M300-14. Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transpo | Cum | 185.4 | Rupees One Hundred Eighty Five and Forty Paise Only |
| 27 | 1111.35 | KSRRB M300- Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet | Cum | 360 | Rupees Three Hundred Sixty Only |
| 28 | 8547.69 | KSRRB M 400-17, Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in unifor | Cum | 1750.5 | Rupees One Thousand Seven Hundred Fifty and Fifty Paise Only |
| 29 | 37327.66 | KSRRB M 500-6, Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kglsqm using mechanical means complete as per specif | Sqm | 29.7 | Rupees Twenty Nine and Seventy Paise Only |
| 30 | 74924.14 | KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatement including cost of all materials, labour, HOM of machineries complete as p | sqm | 3.6 | Rupees Three and Sixty Paise Only |
| 31 | 110736.8 | KSRRB M500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, | sqm | 13.5 | Rupees Thirteen and Fifty Paise Only |

For Benaka Developers And Projects Pvt Ltd.
(Formerly Prajvala Properties Pvt. Ltd.)

Authorised Signatory

Signature of the contractor



27/03

Executive Engineer

27/03

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of D NARAHARI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 32 | 4429.47 | KSRRB M500-19. Providing and laying bituminous concrete 30-40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 5.4% of mix and filler, transporting the hot mix to wo | Cum | 9023.4 | Rupees Nine Thousand Twenty Three and Forty Paise Only |
| 33 | 3618.4 | KSRRB M800-13. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be | sqm | 581.4 | Rupees Five Hundred Eighty One and Forty Paise Only |
| 34 | 19 | Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.48, I. 9.4) PRED.SR 2012-13 | ach B\ | 2016 | Rupees Two Thousand Sixteen Only |
| 35 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 0 to 50m | Rmtr | 327.6 | Rupees Three Hundred Twenty Seven and Sixty Paise Only |
| 36 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 50 to 100m | Rmtr | 428.4 | Rupees Four Hundred Twenty Eight and Forty Paise Only |
| 37 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 100 to 150m | Rmtr | 477 | Rupees Four Hundred Seventy Seven Only |
| 38 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 150 to 200m | Rmtr | 503.1 | Rupees Five Hundred Three and Ten Paise Only |
| 39 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 200 to 250m | Rmtr | 582.3 | Rupees Five Hundred Eighty Two and Thirty Paise Only |

For Benaka Developers And Projects Pvt Ltd.
(Formerly Prajval Properties Pvt. Ltd.)

Signature of the contractor
Authorised Signatory



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of D NARAHARI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 40 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 250 to 300m | Rmtr | 624.6 | Rupees Six Hundred Twenty Four and Sixty Paise Only |
| 41 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - 300 to 350m | Rmtr | 666 | Rupees Six Hundred Sixty Six Only |
| 42 | 950 | Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 - Above 350m | Rmtr | 704.7 | Rupees Seven Hundred Four and Seventy Paise Only |
| 43 | 950 | Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty P. iii, I No. 84 PRED SR 2012-13 | Rmtr | 1419.3 | Rupees One Thousand Four Hundred Nineteen and Thirty Paise Only |
| 44 | 342 | Providing 250mm dia PVC Pipe 6kg/cm SE PRED Approved Rate | Rmtr | 808.2 | Rupees Eight Hundred Eight and Twenty Paise Only |
| 45 | 19 | Providing and fixing 160mm Borewell Cap P. iii, I No. 85 | Rmtr | 107.1 | Rupees One Hundred Seven and Ten Paise Only |
| 46 | 19 | Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by meansns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps PWD SR 2016-17 P. XXXXII Item No. 24 including of all taxes-12.5 HP 25 Stage | No | 79575.3 | Rupees Seventy Nine Thousand Five Hundred Seventy Five and Thirty Paise Only |
| 47 | 4750 | Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008 | Rmtr | 401.4 | Rupees Four Hundred One and Forty Paise Only |

For Benaka Developers And Projects Pvt Ltd.
(Formerly Prajval Properties Pvt. Ltd.)

Signature of the contractor

Authorised Signatory



27/03

Executive Engineer

27/03

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of D NARAHARI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 48 | 836 | Heavy Duty Collar 50 mm dia | No | 139.5 | Rupees One Hundred Thirty Nine and Fifty Paise Only |
| 49 | 9690 | Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 6 Sqm mm KPWD Electrical SR 2014-15 | Mtr | 202.5 | Rupees Two Hundred Two and Fifty Paise Only |
| 50 | 19 | Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09 | Nos | 3213 | Rupees Three Thousand Two Hundred Thirteen Only |
| 51 | 19 | Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wood plugs screws etc., P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15 | Each | 323.1 | Rupees Three Hundred Twenty Three and Ten Paise Only |
| 52 | 570 | Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15 | Mtr | 150.3 | Rupees One Hundred Fifty and Thirty Paise Only |
| 53 | 570 | Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15 | Mtr | 11.7 | Rupees Eleven and Seventy Paise Only |
| 54 | 475 | Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15 | Mtr | 90.9 | Rupees Ninety and Ninety Paise Only |
| 55 | 76 | Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15 - 40mm dia GI pipe | Mtr | 369.9 | Rupees Three Hundred Sixty Nine and Ninety Paise Only |
| 56 | 19 | Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15 - 16Sqmm | No | 299.7 | Rupees Two Hundred Ninety Nine and Seventy Paise Only |
| 57 | 19 | Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, (P No. 55, I No. 7.1) KPWD Electrical SR 2014-15 | No | 2920.5 | Rupees Two Thousand Nine Hundred Twenty and Fifty Paise Only |
| 58 | 114 | Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15 - 32 Amps | No | 192.6 | Rupees One Hundred Ninety Two and Sixty Paise Only |
| 59 | 19 | KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 Page No. 93 Item No. 13.55 / PWD SR 2016-17 | No | 1730.7 | Rupees One Thousand Seven Hundred Thirty and Seventy Paise Only |
| 60 | 19 | Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No. 95 / I. No. 13.81.3 PWD SR 2016-7 | No | 248.4 | Rupees Two Hundred Forty Eight and Forty Paise Only |
| 61 | 76 | Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete | No | 85.5 | Rupees Eighty Five and Fifty Paise Only |

For Benaka Developers And Projects Pvt Ltd.
(Formerly Prajval Properties Pvt. Ltd.)

Signature of the contractor
Authorised Signatory



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of D NARAHARI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 62 | 19 | Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc complete as per specifications | No | 375.3 | Rupees Three Hundred Seventy Five and Thirty Paise Only |
| 63 | 19 | Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps TPN P No. 47 / I No.6.16.5 KPWD SR 2014-15 | No | 1656.9 | Rupees One Thousand Six Hundred Fifty Six and Ninety Paise Only |
| 64 | 416100 | Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete P.No. 49, I. No. 6.40.2 KPWD Electrical SR 2014-15 - 16SWG | No | 0.36 | and Thirty Six Paise Only |
| 65 | 19 | Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. 12.5HP to 15 HP Star Delta Starter SERDED Rate | No | 11781 | Rupees Eleven Thousand Seven Hundred Eighty One Only |
| 66 | 513 | Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil | Cum | 201.6 | Rupees Two Hundred One and Sixty Paise Only |
| 67 | 1140 | Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13. - 75 mm dia 6 KSC PVC pipe | Rmtr | 168.3 | Rupees One Hundred Sixty Eight and Thirty Paise Only |
| 68 | 513 | Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13 | Cum | 65.7 | Rupees Sixty Five and Seventy Paise Only |
| 69 | 38 | KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 92 / 1.13.37 PWD SR - 2016-17 | Each | 2373.3 | Rupees Two Thousand Three Hundred Seventy Three and Thirty Paise Only |

For Benaka Developers And Projects Pvt. Ltd.
(Formerly Prajval Properties Pvt. Ltd.)

Authorised Signatory

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**

27/03

27/03